

MUNICIPALITY OF CLANWILLIAM-ERICKSON

2018 GRAVEL PROGRAM

Quotes will be received by the Municipality of Clanwilliam-Erickson for creating stockpiles of crushed and screened gravel.

1. 7,000 – 10,000 cubic yard stockpile of crushed gravel to specification as follows, completed by August 1, 2018:

Passing Standard Sieves	Crushed Gravel
25 mm Sieve 4.75 mm Sieve (No. 4) 425 um Sieve (No. 40) 75 um Sieve (No. 200)	100% 45 – 70% 10 – 35% 8 – 15%
Minimum Crush Count	25%
Maximum Shale Content	20%

2. 2,000 cubic yard stockpile of screened gravel to specification as follows, completed by July 15, 2018:

Passing Standard Sieves	Crushed Gravel
25 mm Sieve 4.75 mm Sieve (No. 4) 425 um Sieve (No. 40) 75 um Sieve (No. 200)	100% 30 – 70% 5 – 35% 0 – 15%

Bids should be itemized, and bids for either one or both of the above will be considered.

The bid prices shall include all equipment, labour, applicable taxes, levies, permits, and other costs associated with producing the specified aggregate and loading it into a stockpile at the Municipality of Clanwilliam-Erickson gravel pit located at SW 7-18-17W.

MUNICIPALITY OF CLANWILLIAM-ERICKSON

The Municipality of Clanwilliam-Erickson will be responsible for stripping any overburden.

Quotes, clearly marked "GRAVEL STOCKPILE", may be submitted in person during regular office hours and will also be accepted by email and/or post. Quotes must be received at the Clanwilliam-Erickson Municipal Office no later than 5:00 p.m. Central Daylight Time, May 7, 2018.

Council reserves the right to accept or reject any or all quotes or other offers as it may deem in its best interest.

Iain Edge, Assistant CAO
Municipality of Clanwilliam-Erickson
PO Box 40, 45 Main Street
Erickson, MB R0J 0P0
Phone: 204-636-2431
Email: acao@ericksonmb.ca



CLANWILLIAM - ERICKSON

MUNICIPALITY OF CLANWILLIAM-ERICKSON

CONTRACTOR RESPONSIBILITIES

1. Must carry all perils comprehensive public liability insurance at a minimum of \$2,000,000 per occurrence.
2. Must carry appropriate Worker's Compensation coverage.
3. Must produce the aggregate to the specifications called for.
4. Must communicate immediately with the Municipality if there is concern that the material being mined does not allow meeting the specification by crushing or screening.
5. Must mine and produce the aggregate from the pit, and from the specific location within the pit, as directed by the Municipality.

MUNICIPAL RESPONSIBILITIES

1. To test aggregate for compliance with specifications.
2. To provide access to material to be crushed/screened by stripping overburden, and to ensure that aggregate available to be mined where directed by the Municipality will allow the Contractor to produce the crushed/screened product that meets the Municipality's specifications.
3. The Municipality reserves the right to set the total cubic yards of gravel, to an amount deemed suitable by the Municipality.

PAYMENTS AND PENALTIES

1. Payments will be based upon the unit price per cubic yard.
2. The Contractor will make all efforts to complete the work by the specified completion deadline. In the event that the Contractor is unable to meet the deadline specified, a written statement, agreed to by both parties, must be signed to indicate a revised deadline. A penalty of \$200.00 per day may be deducted on final payment for each day the Contractor fails to complete the work by the deadline, excepting Saturdays, Sundays, and Holidays.
3. The Municipality reserves the right to terminate the contract if it is not fully fulfilled after 21 calendar days of the specified completion deadline.