



MUNICIPALITY OF CLANWILLIAM-ERICKSON
CONTRACTOR STREET REPAIR TENDERING DOCUMENTS

REQUEST FOR QUOTATIONS

Quotes are now being accepted to replace two sidewalks in Erickson, MB.

Sidewalk 1: From the intersection of First Avenue SE and Main Street, travelling east approximately 86 feet in distance and 46 inches width, terminating at the eastern edge of the step leading into Erickson Elementary School.

Sidewalk 2: From north edge of Main Street north sidewalk to First Street NW. Two sections separated by a back lane, each section 60 inches wide. One section is 120 feet long, second section is 127 feet long.

Specified Repairs:

- Excavate existing sidewalk and haul away
- Excavate additional 100 mm and haul away
- Haul from municipal stockpile, place, and compact 100 mm A base, adjusting as necessary in Sidewalk 1 location to match existing steps leading into Erickson Elementary School. Stockpile is located 16 km from work sites.
- Supply and place 100 mm fibre-reinforced concrete conforming to the below specification

Concrete Specification:

Nominal Maximum Coarse Aggregate Size	20 mm
Minimum Compressive Strength at 28 days	30 MPa
Minimum Cement Content	310 kg/m ³
Maximum Water to Cementing Materials Ratio	0.45
Air Content	5-8%

- ~ Transverse contraction joints 35 mm deep and 5 mm wide to be located at intervals not more than 5 feet.
- ~ If silty or otherwise unsuitable material located underneath base, contractor to discuss solutions with CAO.
- ~ Work to be started no sooner than July 1, 2020.
- ~ Work to be completed no later than September 1, 2020.
- ~ The contractor will be responsible for obtaining necessary utility locates.
- ~ Separate excavated material where possible.
- ~ Tipping fees waived if waste hauled to Erickson Waste Disposal Grounds.



**MUNICIPALITY OF CLANWILLIAM-ERICKSON
CONTRACTOR STREET REPAIR TENDERING DOCUMENTS**

Quotes marked “Sidewalk Repairs” shall be received by the undersigned until March 10th, 2020 at 4:30 p.m.

Your quote should indicate a price for Sidewalk 1 and Sidewalk 2 together, as well as a price for each sidewalk separately.

Municipality of Clanwilliam-Erickson
45 Main Street, P.O. Box 40
Erickson, Manitoba
R0J 0P0
Phone: 204-636-2431
Fax: 204-636-2516
E-mail: cao@ericksonmb.ca

Council reserves the right to accept or reject any or all quotes or other offers as it may deem to be in its best interest.



MUNICIPALITY OF CLANWILLIAM-ERICKSON CONTRACTOR STREET REPAIR TENDERING DOCUMENTS

CONTRACTOR RESPONSIBILITIES

- 1.1 Must carry all perils comprehensive public liability insurance at a minimum of \$1,000,000.
- 1.2 Must carry appropriate Worker's Compensation coverage.
- 1.3 Will assume the responsibility for the safety of the jobsite and ensure all workers or the public are protected from hazards.
- 1.4 Will not operate any equipment or machinery in such a way that creates a noise nuisance before 7:00 am or after 11:00 pm. A violation of this clause shall result in a penalty of \$200 for each day a violation occurs and will be deducted from the final payment.
- 1.5 Once the job has commenced, it must be continuous until completion except in inappropriate weather conditions.
- 1.6 Must complete the job to the date specified in the tender. Should the job be completed after the specified deadline, a penalty of \$200 per day will be assessed and deducted from the final payment.
- 1.7 The assessment of charged days will be stopped the day after the street under construction is open to vehicular traffic and all deficiencies have been addressed.
- 1.8 Of the excavated material, the asphalt will be separated from base material.

MUNICIPAL RESPONSIBILITIES

- 1.9 Will exercise a 10% hold back upon receiving an invoice from the contractor.
- 1.10 Upon satisfactory completion of the project, the 10% hold back will be issued in full to the contractor, except for an instance as specified in clause 1.6, the remaining hold back sum may be less.